

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Ontonagon <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 15 T 51N R 37W	8
	S _____ T _____ R _____	(GCDB 420440)
	S 15 T 51N R 37W	5
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	(GCDB 440460)
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 8 08/19/15 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- (8-Sec. 15) Center-West 1/16 corner, Section 15. Not previously monumented.
 - (5-Sec. 15) Center-North 1/16 corner, Section 15. Not previously monumented.



- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- (8-Sec. 15) Established the position for the corner midway and on a straight line between Quarter corner 1323.11' west and the Center of Section 15 1323.11' east.
 - (5-Sec. 15) Established the position for the corner midway and on a straight line between Quarter corner 1302.32' north and the Center of Section 15 1302.32' south.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- | | |
|---|--|
| <ul style="list-style-type: none"> (8) Set 1"IDx28" I.pipe with 2" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 4" Sugar S70°E 3.05' mrkd "1/16S BT" 3" Sugar S24°W 15.15' do 4" Sugar S86°W 2.6' do 3" Ash N03°W 18.6' do Sq'd a 3" Sugar N50°E 3.3' for a post. E= 7848143.076 N= 227751.676 | <ul style="list-style-type: none"> (5) Set 1"IDx28" I.pipe with 2" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 10" twin Sugar N20°E 8.75' mrkd "1/16S BT" 5" W.Pine S74°E 11.6' do 14" Sugar S29°E 20.15' do 7" W.Pine N69°W 14.0' do Sq'd a 6" Balsam N15°W 1.2' for a post. E= 7848570.473 N= 228157.118 |
|---|--|

Bearings are magnetic. Coordinates are MCS83 in meters, NAD83(2011) Epoch 2010.00 datum.
 Coord. Ref.=NGS PID RL0593: N= 221669.506 m. E= 7868965.488 m.

Signed by Stephan J. Szyszkoski Date 08/26/2015
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Forest Resources Division