

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Ontonagon County Remonumentation Corner

Ontonagon County LC 5/141
REC'D, Rec. Date 08/26/98 Time 13:29
RECORDING FEE: 9.00

For corners in

Table with columns: Ontonagon County, Located in:, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec., Lot No., and Private Claims.

Register of Deeds Stamp & File Number. Includes a grid for recording details and a signature area.

I, Joseph C. Domitrovich, in a field survey on August 12, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A-10) 1/4 Corner Common to Section 25, T51N, R38W & Section 30, T51N, R37W

1845 - Austin Burt set a post.

- 10" Sugar S 25° W 18 links (11.88')
12" Hemlock N 52° W 34 links (22.44')

1976 - Keith Sackett, P.S. 19006, for Michigan DNR, found a 1" I.D. Iron pipe and also a hemlock log with scribing— possible original bearing tree. He established three N.B.T.s: 14" Y. Birch N 10° W 28.8', 12" Sugar S 25° E 21.8', 22" Sugar S 22° W 13.0'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

At the corner I found the pipe as called for by Sackett and the rotted remains of a fallen 14-16" Hemlock at the position of the original Hemlock B.T. I found all three of Sackett's N.B.T.s. His 22" Sugar N.B.T. falls at the position of Austin Burt's original B.T. and could very possibly be the same tree. The distance South to the Southeast Corner and distance North to the Northeast Corner work well with GLO.

I accepted the pipe as the corner and have monumented it as such.

Research on file with County Remonumentation Representative.

PEER GROUP APPROVED
Paul W. Applekamp
COUNTY REGISTERED
8-19-98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 3/4" x 36" aluminum rod driven inside the 1 1/4" O.D. pipe, with a 3" diameter aluminum cap stamped to read: COUNTY REMONUMENTATION; S.25, S.30; 1/4; T.51N, R.38W, R.37W; 1998; P.S. 37273.

Witnesses:

Table with columns: Witness, Bearing, Distance, Notes. Includes entries for 18" Twin H. Maple, 14" H. Maple, 24" H. Maple, 16" Y. Birch, Steel Sign Rail, NE Cor. Section 25, and SE Cor. Section 25.

NOTE: Bearings to witness objects are magnetic. Distances are to a nail in side of the witness object unless noted.

Signed by [Signature] Date 8-19-98

Surveyor's Michigan License No. 37273