

JUDITH D. ROEHM
LAND CORNER RECORDATION CERTIFICATE Ontonagon County
 Filing Requirement of Act 74, Mich. P.A. 1970 of 1 LC 5/ 89
 Ontonagon County Remonumentation Corner
 Rec. Date 06/25/98 Time 12:08
 RECORDING FEE: 9.00

For corners in
 Ontonagon County Located in: Corner Code #
 1. Public Land Survey T51N R37W C-13
 T R
 T R
 2. Property Controlling S T R
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R
 4. Lot No. Recorded Plat
 5. Private Claims

REGISTERED
 JAN 11 1999
 SECTION
 Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Joseph C. Domitrovich, in a field survey on June 11, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
(C-13) Standard Corner Common to Sections 31 & 32, T51N, R 37W
 Corner is on the 5th Correction Line.

- 1845 - Austin Burt set a post.
 10" Lynn N 49° E 26 links
 8" Hemlock N 34° W 21 links
 At 8.00 chains (528') to West, he intersected a ridge of trapose rock, course N-S.
- 1939 - Copper Range Corner Records: A 1" iron pin was found 6" above ground.
 They marked a 6" Basswood N 11° E 28 feet and a 6" Elm N 51° W 23 feet.
- Undated - Old Mining Map, on file with Steve Hein, P.S. 32336, shows this corner and distances to corners East and West.
- 1976 - Keith Sackett, P.S. 19006, for Michigan DNR, found 1" steel pin. The corner is recorded at Ontonagon County Register of Deeds, Liber 1, Page 57 of Corner Records. He also established 3 scribed N.B.T.s:
 5" Sugar N 25° W 14.5'
 7" Yellow Birch N 60° E 12.7'
 8" Sugar S 16° W 13.1'

PARA GROUP APPROVED
Earl W. Applekamp
 COUNTY REGISTER OF DEEDS 6-17-98

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

I found no remains of original corner or accessroles. I found a 1" iron pin as called for by Copper Range and Sackett. I found an Elm stump N51° W 23' as per Copper Range. I recovered remains of Sackett's N.B.T.s. The Yellow Birch is down and rotten. The 8" Sugar is dead but still standing. Distance East to the ridge call works well (520' measured). Distances to corners East and West on the Correction Line work well with Old Mining Map distances:
 S 1/4 Corner Section 31 N 89° 43' 05" W 2654.84' (meas.) 2657.0' (old map)
 SE Corner Section 32 N 89° 42' 46" E 5315.70' (meas.) 5315.7' (old map)
 I accepted the iron pin as the Standard Section Corner.
 Research on file with County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 2 1/2" x 30" aluminum pipe with a 3" diameter aluminum cap placed over the 1" iron pin. The cap is stamped to read: COUNTY REMONUMENTATION; S. 32, S. 31; S.C.; T.51N, R.37W; 1998; P.S. 37273. Corner falls 6 feet South of an East-West fence.

- Witnesses:
- 10" Basswood S 80° E 9.13' (existing blaze and aluminum tag)
 - 6" Hard Maple S 11° W 22.01'
 - 4" Hard Maple S 70° W 13.85'
 - 6" Hard Maple N 22° W 15.01' (DNR -- 14.5' to face)
 - Steel Sign Post North 0.95' (to face)

NOTE: Bearings to witness objects are magnetic. Distances are to a nail in side of the witness object unless noted.

Signed by Joseph C. Domitrovich
 Surveyor's Michigan License No. 37273

Date 6-17-98

