

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Ontonagon County Remonumentation Corner

Ontonagon County of 1 LG 5/ 90
Rec. Date 06/25/98 Time 12:09
RECORDING FEE: 9.00

For corners in

Ontonagon County	Located in:	Corner Code #
1. Public Land Survey	T51N R37W	E-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No.	Recorded Plat	
5. Private Claims		

REGISTERED
JAN 11 1999
SECTION
Register of Deeds Stamp & File Number

I, Joseph C. Domitrovich, in a field survey on June 11, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
(E-13) Standard Corner Common to Sections 32 & 33, T51N, R37W
Corner is on the 5th Correction Line

1845 - Austin Burt set a post.

10' Sugar N 68° E 34 links
8' Sugar N 57° W 12 links

Undated - Old Mining Map on file with Steve Hein, P.S. 32336, shows this corner and distance West to the Standard Corner of Sections 31 & 32.

1980 - Keith Sackett, P.S. 19006, for Michigan DNR, found a 1/2" I.D. iron pipe at old fence corner as called for by the Highway Department. The corner is recorded at Ontonagon County Register of Deeds, Liber 1, Page 207 of Corner Records. He established three scribed N.B.T.s:

8" Sugar S 27° E 13.5'
7" Sugar S 65° W 6.4'
12" Sugar N 38° W 20.5'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found no remains of original corner or accessories. I found a 1/2" O.D. iron pipe at the intersection of old fencelines to the North, East and West as called for by Sackett. I recovered his three N.B.T.s. The Sugars to the SE and NW are dead but standing. Distance West to Standard Corner works well with old map distances. Distances East and West to 1/4 Corners also work well:

SW Cor. Section 32 S 89° 42' 46" W 5315.70' (meas.) 5280' (GLO) 5315.7' (old map)
S 1/4 Cor. Section 33 N 89° 50' 06" E 2642.30' (meas.) 2640' (GLO)
S 1/4 Cor. Section 32 S 89° 40' 01" E 2657.85' (meas.) 2640' (GLO)

I accepted the pipe as the Standard Section Corner and replaced it with a county monument.

Research on file with County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 2 1/2" x 30" aluminum pipe with a 3" diameter aluminum cap stamped to read: COUNTY REMONUMENTATION; S.32, S.33; S. C.; T.51N, R.37W; 1998; P.S. 37273.

Witnesses:

8" Hard Maple S 74° E 12.64'
7" Hard Maple S 66° W 6.68' (DNR - 6.4' to face)
5" Ironwood N 45° W 8.57'
Steel Sign Post N 55° E 1.13' (to face)

NOTE: Bearings to witness objects are magnetic. Distances are to a nail in side of the witness object unless noted.

Signed by Joseph C. Domitrovich

Date 6-17-98

Surveyor's Michigan License No. 37273

