

JUDITH D. ROEHN  
 LAND CORNER RECORDATION CERTIFICATE (Ontonagon County)  
 Filing Requirement of Act 74, Mich. P.A. 1970 of 1 LC 5/ 91  
 Ontonagon County Remonumentation Corner Rec. Date 06/25/98 Time 12:09  
 RECORDING FEE: 9.00

For corners in

Ontonagon County	Located in:	Corner Code #
1. Public Land Survey	T51N R37W	I-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

CLERK OF COUNTY REGISTER  
 JUDITH D. ROEHN

JAN 11 1999

SECTION

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Joseph C. Domitrovich, in a field survey on June 11, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
(I-13) Standard Corner Common to Sections 34 & 35, T51N, R37W  
 Corner is on the 5<sup>th</sup> Correction Line.

1845 - Austin Burt set a post.  
 6" Aspen N 72° E 22 links  
 10" Aspen N 48° W 23 links

1955 - Michigan State Highway Department, in M-35 Highway Plans project 66-15 show an iron pipe at this corner. They give distances to centerline to the North and to a pipe at the S ¼ Corner to the East.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found no remains of original corner or accessories.

I found a 1 ¼" solid iron pin at the corner position. Lines are ribboned in three directions from it. I found three blazed trees facing it, two with nails and tags in the side. It appears this corner has been accepted and used for many years. Distances to ¼ corner to the East works well: N 89° 50' 45" E 2635.40' (meas.) 2640.32' (M.S.H.D.)

It also works well with corners on Correction Line 1 ½ miles to the West. I accepted the iron pin as the Standard Corner.

Research on file with County Remonumentation Representative.

PEER GROUP APPROVED  
*Earl W. Applekamp*  
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: 6-17-98

Corner is a 2 ½" x 30" aluminum pipe placed over a 1 ¼" iron pin. It has a 3" diameter aluminum cap stamped to read: COUNTY REMONUMENTATION; S. 35, S. 34; T.51N, R.37W; S.C.; 1998; P.S. 37273.

Witnesses:

6" Hard Maple	N 83° E	22.85'	
7" Spruce	S 70° E	13.90'	(found nail and tag)
9" Cedar	S 25° E	4.90'	(existing blaze grown over)
Steel sign post	South	1.34'	
10" Basswood	N 50° W	5.94'	(found nail and tag)
11" Cedar	N 12° W	21.32'	



NOTE: Bearings to witness objects are magnetic. Distances are to a nail in side of the witness object unless

Signed by Joseph C. Domitrovich

Date 6-17-98

Surveyor's Michigan License No. 37273