

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Ontonagon

(County)

Located In:

Corner Code #

**1. Public Land Survey**

T	51N	R	37W	K7
T	51N	R	37W	K8
T		R		
T		R		

**2. Property Controlling in Section**

S		T		R	
S		T		R	
S		T		R	
S		T		R	

**3. Miscellaneous Property in Sec.**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Sep 20 2004

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	19		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

(K7) Corner common to Sections 13-14-23-24. 1976 - K.L. Sackett Found and accepted a 1" ID iron pipe. 3" Hemlock S18E 3.6', 12" Y.Birch S75W 3.7', 14" Sugar N57E 26.5'.

(K8) Quarter corner common to Sections 23-24. 1846 - Established by S.W.Higgins Deputy Surveyor: North between Sections 23 & 24 ... 15.00 Stream 6 W...40.00 Set 1/4 sec. post. Y.Birch 12 N80W 30, Y.Birch 12 S68E 22 ... 50.40 Stream 2 W in ravine ... 69.49 Stream 4 W in ravine ...80.00 Set post on level ground bet. Secs. 13, 14, 23, 24.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(K7) Found and accepted a 3/4" ID thick-walled pipe, in good condition, likely the pipe noted in the 1976 record, at record bearing and distance from the 1976 NBTs, all in good condition with overgrown blazes. The NBTs Hemlock SE and Y.Birch SW were cut down during this survey to facilitate GPS observations. Left the pipe in place and made new witnesses as described below.

(K8) Recovered fragments of a post point, likely the original, with axe marks, at record bearing and distance from the rotting remains of two Y.Birch stumps, likely the original BTs. Y.Birch S73E 14.5' is a rotting stump with some solid wood and bark. Y.Birch N82W 19.8' a rotting mound. Both stream calls to the north check very well with the record from this position. The stream call south is obliterated by beaver workings. I accepted the post point as the best available evidence of the position of the original corner and replaced it with a monument as described below.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(K7) Found 3/4" ID thickwall pipe. Set measuring nails in the following marked trees:

7" Maple S29E 25.4' "S24 NBT"  
 9" Hemlock N75W 32.8' "S14 NBT"  
 11" Y.Birch N54W 32.2' "S14 NBT"  
 17" Sugar N58E 26.9' overgrown blazes  
 A sq'd Cedar post is adjacent. Bearings are magnetic. Distances are to nail with tag.

(K8) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in the following marked trees:

14" W.Spruce N50E 22.5' "1/4S NBT"  
 12" Cedar S39E 12.8' do  
 15" Hemlock S86W 25.3' do  
 18" Y.Birch N12W 43.4' do  
 Sq'd Cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 11/3/04