

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ontonagon

(County)

Located In:

Corner Code #

1. Public Land Survey

T ___ R ___
 T ___ R ___
 T ___ R ___
 T ___ R ___

2. Property Controlling in Section

S 35 T 51N R 37W 12
 S 35 T 51N R 37W 8

3. Miscellaneous Property in Sec.

S ___ T ___ R ___
 S ___ T ___ R ___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Sep 23 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | | | | | | | | | | | | | |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:
 (12-Sec. 35) South 1/16 corner, Sec. 35. Not established in the original survey.
 (8-Sec. 35) West 1/16 corner, Section 35. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(12-Sec. 35) Established the corner midway and on a straight line between Center of Section 1329.89' north and Quarter corner 1329.89' south. The position for the corner falls in Simar Airport Road, west of center.
 (8-Sec. 35) Established the corner midway and on a straight line between Ontonagon County Quarter corner of record 1358.46' west and Center of Section 1358.46' east. From the position thus established, I found a 2" ID iron pipe, not of record, N19W, 10.3' distant.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| | |
|--|---|
| (12) Set 1" IDx32" I. pipe with 4" alum. MDNR cap. Set measuring nails with tags in: 8" W. Pine N44E 45.1' 5" W. Pine S78E 29.0' 7" Oak S32W 67.8' 5" Maple N86W 24.6' Bearings are magnetic. Distances are to nail with tag. | (8) Set 1" IDx32" I. pipe with 4" alum. MDNR cap. Set measuring nails with tags in: 6" Spruce N02E 28.3' mrkd "1/16S BT" 5" Maple S61E 11.0' do 8" Sugar S33W 15.9' do 10" Maple N82W 7.7' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. |
|--|---|



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 11/3/04