

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ontonagon

(County)

Located In:

Corner Code #

1. Public Land Survey

T 51N R 37W J12
 T R _____
 T R _____
 T R _____

2. Property Controlling in Section

S 35 T 51N R 37W 11
 S T R _____
 S T R _____

3. Miscellaneous Property in Sec.

S T R _____
 S T R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

J12 Sep 29 2004

11 Sep 23 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

(J12) Center of Section 35. Not established in the original survey.

(11-Sec. 35) Southwest 1/16 corner, Section 35. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J12) Established the corner at the intersection of straight lines connecting opposite 1/4 corners. The position for the corner falls in the west shoulder of Airport Road, approx. 9' west of the centerline in fill above a culvert containing a small stream approx. 12' below the corner position. Drove the monument to about 4" below road grade.

(11-Sec. 35) Established the corner at the intersection of straight lines connecting opposite 1/16 corners. From the position thus established, an old 1" ID iron pipe, not of record, situated in a line of posts to the south, bears N41W 9.1' distant. Recovered evidence of old fencing running east, 6' north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J12) Set 1" IDx32" I. pipe with 4" alum. MDNR cap. Set measuring nails with tags in:

9" dbI Maple N41E 60.3' mrkd "C1/4 BT"
 9" Maple N82E 28.5' do
 5" Spruce S27W 33.5' do
 11" W. Pine N61W 20.0' do

Bearings are magnetic. Distances are to nail with tag.

(11) Set 1" IDx32" I. pipe with 4" alum. MDNR cap. Set measuring nails with tags in:

7" Maple N62E 12.7'
 21" W. Pine S50E 19.4'
 6" Hemlock S60W 15.7'
 7" Maple in clump N43W 12.4'

Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 11/3/04