

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Ontonagon

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>51</u> N R <u>37</u> W	I12
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Sep 15 2004

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34	●	35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

(I12) Quarter corner common to Sections 34-35. 1998 - Reestablished by J.Domitrovich PS37273 midway and on line between Section corners. Approved by Ontonagon Co. Peer Group 7/22/98. Rec. in L5 P126 of Land Corners, Ontonagon County Records. 2.5"x30" aluminum pipe with 3" dia. alum. cap. 15" W.Pine S51W 31.46, 8" Balsam N83W 25.24', SE Cor. Log Cabin N29W 94.10, Power Pole N43E 19.89', Steel Sign post East 6.53', NW Cor. Section 35 N01 deg. 19'17"W 2655.50', SW Cor. Section 35 S01 deg. 19'17"E 2655.50'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(I12) Found and accepted the 1998 monument in good condition and at record bearing and distance from the 1998 witnesses. Observed bearings and distances to adjacent section corners are N01 deg. 13'07"W 2655.77' to I11 and S01 deg. 12'53"E 2655.52' to I13. Found a 2"ID iron pipe, not of record, N48W 18.4' distant. Found a 1.5"ID iron pipe, not of record, N46W 48.0' distant. Left the monument in place and made additional witnesses as described below. All bearings stated in this section are True.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(I12) Found 2.5" dia alum. pipe with 3" alum. Ontonagon County cap. Set measuring nails with tags in the following new witnesses:

6" Elm S80W 24.3' mrkd "1/4S N8T"  
 11" W.Spruce N65W 55.4' do  
 15" W.Pine N36W 64.3' do

Power Pole M837635 N42E 20.0'

The 1998 witnesses are still in place.

Bearings are magnetic. Distances are to nail with tag.

Signed by Stephan J. Szyszkoski

Date 11/3/04

Surveyor's Michigan License No. 33986

