

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Ontonagon Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

- |                                    |      |             |          |
|------------------------------------|------|-------------|----------|
| 1. Public Land Survey              | T    | R           | _____    |
|                                    | T    | R           | _____    |
|                                    | T    | R           | _____    |
|                                    | S 30 | T 51N R 37W | B10      |
| 2. Property Controlling in Section | S 30 | T 51N R 37W | E-W 1/64 |
|                                    | S    | T           | R        |
| 3. Miscellaneous Property in Sec.  | S    | T           | R        |
|                                    | S    | T           | R        |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims

I, Stephan J. Szyszkoski, in a field survey on March 5, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		20		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 (B10) Center of Section 30. Not established in the original survey.


(E-W 1/64)- East-West 1/64 corner on the E-W 1/4 line of Section 30. Being the NE corner of the W1/2 of the NE1/4 of the SW1/4 of Sec. 30. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 (B10) Found a 1/2" dia. rebar with plastic cap # 37273 (Joseph Domitrovich PS) at the intersection of 1/4 lines. Accepted same as a careful and faithful establishment of the position of the corner.

(E-W 1/64) Found and accepted a 1/2" dia. rebar capped with a plastic cap stamped "PS 37273" (Joseph Domitrovich) on the E-W 1/4 line of Section 30, 668.04' west of the Center of the Section and 2102.53' East of the Quarter corner A10. Accepted same as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 (B10) Found 1/2" rebar with cap #37273. (1/64) Found 1/2" rebar with cap #37273.  
 Set measuring nails with MDNR tags in the sides of: Set measuring nails with MDNR tags in:  
 5" Hemlock N04E 11.4' mrkd "C1/4 BT" 12" Sugar N25W 5.2' mrkd "1/64S BT"  
 4" Balsam S89E 6.1' do 7" Ironwood S87E 6.3' do  
 9" Ironwood S15W 5.2' do 11" Sugar S17W 17.9' do  
 5" Sugar S82W 18.3' do 6" Sugar N80W 20.5' do  
 Found wooden lathe adjacent. Bearings are magnetic. Found wooden lathe adjacent. Bearings are magnetic.  
 Distances are horizontal, taken to nail in side of Tree. Distances are horizontal, taken to nail in side of tree.

Signed by Stephan J. Szyszkoski



Date 9/5/07

Surveyor's Michigan License No. 33986