

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Ontonagon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T51N R 37W	C9
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File
Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Stephan J. Szyszkoski, in a field survey on March 5 2007, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 (C9) Corner common to Sectionsw 19-20-29-30. 1846 - Established by S.W. Higgins, Deputy Surveyor. Set Post. Hemlock 30 N50W 11 links, Sugar 10 S20E 20 links. 1940 - Notes of Copper Range Company (probably by W.A.Waara, RLS) state: Found 1" I.pipe 1 ft. above ground for Cor. Found 24" Hem. BT (stdg) N70E 47' chopped out old scribe marks plainly visible. Found 18" S.Map. stump (sawed) BT marks visible S59E 13.8' from I.P. Fd. 14" Y.B. (stdg) blazed by several cruisers N46E 13'. Marked 6" Y.B. S61E 21.5' from I.P. 1943 - Add'l CRC notes: Fd 1" IP for cor. Fd. 18" sawed S.Map. stp. BT marks vis. S61E 31 lnks. Fd 30" sawed hem. stp. BT marks vis. N62E 47' Put Y.tag on 5" YB S16E 30 lnks. Cor. is on E edge Siren log rd...Note: WAW moved this cor. 13 links due East of where it should be, because it would have been pulled out in logging. All Brg's are taken from where Cor. should be. 1976 - K.L.Sackett RLS fd. 1" ID pipe with 1940 Y.B. 20" N46E 13.0' (dead ref. tree stub) in place. Set MDNR monument at pipe (in E rut logging rd). 12" W.Birch S2E 40.3', 8" Sugar S51W 43.6', 20" Y.Birch N46E 13.0'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (C9) Found the 1976 monument in good condition at record bearing and distance from the 1976 NBTs S2E 40.3' and N46E 13.0' (now both dead) and NBT Sugar S51W 43.6' in good condition. I note that the trees described as "BT" in the CRC notes of 1940 and 1943 are not to be found in the GLO record. There remains the possibility that the monument found and perpetuated in 1976 was that placed 13' east of where the corner "should be", as described in the 1943 record. The corner area has been worked by logging and cleared by heavy equipment. None of the other witnesses of record were found and, therefore, cannot help remove the doubt. I presume that the monument has been removed to its "proper position" in the years since 1943 and note that the 1940 witness tree Y.Birch N46E 13.0' was recovered in 1976 and its remains are still in place at record bearing and distance this date. I also note that W.A.W stated clearly in 1940: "Fd. 1" I.pipe 1 ft. above ground for Cor." and have no clear reason to doubt that his measures to the Y.B. N46E were not taken from that position. Having found nothing to firmly support the notion that the recovered monument marks the 13' offset position noted in 1943, I accept the monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (C9) Found 1" ID I.pipe with 4" alum. MDNR cap. Set measuring nails with MDNR tags in the sides of:
 12" Sugar S53W 43.8' healed blazes (1976 wit)
 12" Y.Birch N35W 30.9' mrkd "S19 NBT"
 8" Sugar N43E 15.0' mrkd "S20 NBT"
 7" Sugar S11E 42.5' mrkd "S29 NBT"
 Bearings are magnetic. Distances horizontal, taken to nail in side of tree.



Signed by Stephan J. Szyszkoski Date 9/5/07

Surveyor's Michigan License No. 33986