

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Ontonagon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>51N</u> R <u>37W</u>	<u>I8</u>
	T <u>51N</u> R <u>37W</u>	<u>H8</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

H8 Jun 07 2006
 I8 May 30 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(I8) Quarter corner common to Sections 22 and 23. 1846 - Established by S.W.Higgins, Deputy Surveyor: North between Sections 22 & 23 ...40.00 Set 1/4 Sec. post. Balsam 9 S88E 27 links, Sugar 6 N20W 37 links. ...80.00 Set post cor. Sec 14, 15, 22 & 23. Found no subsequent record.
 (H8) Center of Section 22. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I8) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner midway and on a straight line between Section corners 2664.53' north and south.
 (H8) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I8) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 9" W.Spruce N52E 37.9' mrkd "1/4S NBT" 5" Maple S30E 28.6' do 7" Maple S37W 24.5' do 7" Aspen N48W 13.8' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.	(H8) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 8" Sugar N40E 24.7' mrkd "C1/4 BT" 12" Sugar S84E 17.4' do 10" Sugar S40W 14.3' do 8" Sugar N81W 9.9' do set sq'd spruce post adjacent. Bearings are magnetic. Distances are to nail with tag.
---	---



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 6/19/06