

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Ontonagon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>12</u> T <u>51N</u> R <u>37W</u>	<u>1/64 S. of K4</u>
	S <u>12</u> T <u>51N</u> R <u>37W</u>	<u>L2</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2			
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 1/64 06/08/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(N-S 1/64 between 11 and 12) 1/64 corner on the Section line between Sections 11 and 12, being the SW corner of the NW1/4 of the NW1/4 of the SW1/4 of Section 12. 1977 - Established by K.L.Sackett RLS. Set 1"IDx36" I.pipe with 4" aluminum cap. 6" Balsam N85E 21.3', 8" Sugar N62W 17.6', 7" Sugar S57W 10.4'.

(L2) Center of Section 1. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(N-S 1/64) Found the 1977 monument in good condition, 1.4' N. of the southerly edge of a beaver flooding, cap projecting 3" above the surface of the water, which is 6" deep at the corner position. The Sugar BT SW was found in good condition, at record bearing and distance, with overgrown blazes. Accepted the monument as a careful and faithful establishment of the position of the corner.

(L2) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(N-S 1/64) Fd. 1"ID I.pipe with 4" MDNR cap. Set measuring nail with MDNR tag in the side of:
 8" Maple S62W 10.55' old blazes (1977 BT)
 5" Maple N72W 15.95'
 11" Maple S12E 15.0'
 4" Spruce S64E 31.4'
 Set sq'd Cedar post adjacent.
 Bearings are magnetic.

(L2) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 8" Cedar S54W 12.55' mrkd "C1/4 BT"
 9" B.Spruce S86W 6.9' do
 7" B.Spruce N28W 12.85' do
 4" Sugar S63E 19.25' do
 Set sq'd Cedar post adjacent.
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 06/16/2009



For the Michigan Department of Natural Resources, Office of Land and Facilities