

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Ontonagon COUNTY
T 51 N R 38 W

DESCRIPTION OF CORNER 1/4 corner between Section 35 and 36

CORNER MONUMENT 4" aluminum cap embedded in concrete in bedrock

DATE MONUMENT PLACED AND WITNESSED September 10, 1970

WITNESSES TO CORNER..... W. Spruce 9 N5°W (mag.) 19.3 ft.* "1/4S, NBT"



+ Chiselled in rock face N12°W (mag.) 30.8 ft.*

Hemlock 6 N55°E (magnetic) 14.0 ft.** "1/4S, NBT"

AND * Approximately horizontal measurement
** Slope distance

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner established by triangulation from a traverse between section corners to north and south. Distance between section corners was found to be 5276.7 feet, with 1/4 corner position calculated to be at midpoint on line. As this corner is in a place inaccessible by direct measurement, it was established by intersecting transit angles from a base line 500-600 feet to the northeast. While done as precisely as conditions permitted, the corner is not guaranteed to be exactly at the calculated position. Corner is on a small rock ledge on the east face of Adventure Bluff.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE December 17, 1971

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68