

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


Ontonagon COUNTY  
T 51N R 38W

DESCRIPTION OF CORNER Section Corner between Sections 35 and 36

CORNER MONUMENT 1/2" solid round iron rod

DATE MONUMENT PLACED AND WITNESSED May 13, 1970

WITNESSES TO CORNER..... NW corner of main foundation of St. Paul's Lutheran Church,  
S71 $\frac{1}{2}$ <sup>o</sup>E (mag.) 117.50 ft.



SE corner of concrete foundation of a garage,  
N67<sup>o</sup>W (mag.) 20.00 ft.

NE corner of foundation of rear extension of house,  
S28<sup>o</sup>W (mag.) 74.30 ft.  
AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a 1/2" solid round iron rod in place, which agrees with location described in Plat of Village of Mass City.

Accepted corner as found. Monument pointed out to Survey Party Chief K. Sackett by long-time local residents. Not a plat corner, but position is indicated on the plat. Corner is on rear line of Lot 10, Block 66, Plat of village of Mass City. This corner is common only to Sections 35 and 36, T51N, R38W, as it lies on the Fifth Correction Line.

SURVEYOR'S SEAL

SIGNED

*Arthur O. Enger*  
REGISTERED LAND SURVEYOR  
Arthur O. Enger

DATE

December 17, 1971

DISTRIBUTION:

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68