


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Ontonagon COUNTY
T 51 N R 38 W

DESCRIPTION OF CORNER Center of Section 35
CORNER MONUMENT Cross (+) chiselled on a rock is the corner.
Set a 1" I.D. x 36" iron pipe with 4" aluminum cap 1.3 feet south of
cross for a witness corner.
DATE MONUMENT PLACED AND WITNESSED May 13, 1970
Iron Pipe
WITNESSES TO CORNER..... Red Oak 7 N64 $\frac{1}{2}$ °E (mag.) 40.2 ft. "1/4S, NBT"



Elm 8 N83°E (mag.) 71.7 ft. "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a cross (+) chiselled on a rock, pointed out to Survey Party Chief K. Sackett by a long time local resident, Mr. Nick Lukkarilla, as being the center of the section. Measurements along E & W 1/4 line and East section line tend to support the location.

Corner accepted as found.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE

December 20, 1971

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68