

5.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Ontonagon
 (County)

Located in:

Corner Code #

1. Public Land Survey	T 51N R 38W	K12
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Oct 07 1996

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (K12) Quarter corner common to Sections 35-36. Corner reestablished in 1970 by A.O. Enger, RLS, at a position proportionate to the original record between Sections corners 1/2 mile north and south. The location of the position was determined by triangulation. 1970 witnesses: N. Spruce 9 NSN 19.3', + chiselled in rock face N12W 30.8', Hemlock 6 N55E 14.0' (slope dist.). The corner position was marked by a 4" dia. aluminum cap embedded in concrete on a small rock protruding from the east face of Adventure Bluff. Enger notes the distance between section corners to be 5276.7'. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K12) Found the 1970 monument, as described, in good condition, and at record bearing and distance from all three 1970 accessories. The Spruce is windthrown but the Hemlock is standing in good condition, with the 1970 blazes grown over. I surveyed to this corner, and to the adjacent section corners, from GPS control established near all three. I found this monument to be 0.5' North and 8.7' West of the proportionate position intended to be monumented in 1970. Considering the severity of the terrain, and the measuring technique used in 1970 to position the monument, I accepted the monument as a careful and faithful reestablishment of the position of the original corner. Left the monument in place and marked two new bearing trees as described below. Access to this corner is best from the Northeast, along and up a faint trail and eventually through a short cave-like adit cut into the bluff, which also contains a narrow shaft apparently leading to workings below. The adit is nearly due north of the corner, and is quite close to it. The small rock ledge in which this monument is fixed is about 3-4' below and about 4' above ground upon which fairly good footing can be had. The overall distance between section corners north and south was found to be 5273.41'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K12) Found a 4" dia. aluminum HDRA tablet concreted into a small rock ledge. Blazed and scribed the following new bearing trees:

6" N. Oak N85W 7.4' 1/4S HBT
 10" N. Pine S25W 10.4' 1/4S HBT

The 1970 witnesses:
 8" Hemlock N55E 14.0' (slope)
 + cut in rock face N12W 30.8'

Bearings are magnetic. Dist. Horizontal unless noted.

Signed by Stephan J. Szyszkoski

Date Sept. 17, 1997

Surveyor's Michigan License No. 33986



For the Michigan Department of Natural Resources - Forest Management Division