

6.

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ontonagon

(County)

Located in:

Corner Code #

1. Public Land Survey

T 51N R 38W I12

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling  
in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous  
Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Oct 07 1996

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:  
(I12) Quarter corner common to Sections 34-35. Original corner established in 1846 by H. Higgins and S.W. Higgins: "...40.00 Set 1/4 Section post Hemlock 12 S75W 20, do 12 N15E 40". Corner shown on Plat of Jeff's Addition to Maple Grove as being on the West side of Main Street: An angle is shown to this corner on a sap by J.E. Vause, C.E. (Map #132, Ontonagon Co. Reg. of Deeds plat cabinet) from the North line of the Section, it being 94 deg. 44 min. Corner shown in MDSH records dated 8-1-66 by C.C. Lindgren RLS 14098: "Set 1" iron pipe, 9' south of the centerline of East-West Drive. 20' West of center line of blk. top county road. Witnesses are T. Pole S15W 22.68', P. Pole S55E 48.02', Guy Pole N05E 33.02'". MDSH measurement to I11 is 2653.50'. Corner shown on survey drawing by Earl Applekamp, RLS 17610 August 22, 1978 as a 1 1/2" pipe located 2653.99' South of I11. 5/8" iron pin reported found by Joe Domitrovich, PS 37273, in 1996.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I12) Found a 5/8" iron pin placed in new road fill. MDSH witnesses no longer exist. Determined angle at I11 from J11 to the pin to be 94 deg. 43 min. 25 sec. and distance north to I11 from the pin to be 2653.14'. The west edge of blacktop of N-S county road is 10' east. The centerline of a two-track to the west is North 9'. I accepted the position of the pin as being that monumented in 1966 by the Michigan State Highway Department and as being the best available evidence of the position of the original corner. Left the pin in place and made new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
(I12) Found 5/8" iron pin.

Face of P. pole #90-21941 S55E 46.8'  
Face of P. pole #90-23338 S12W 25.9'  
SE corner found'n House #701 N2W 90.5'  
SW cor. found'n House #700 N44E 131.5'  
Bearings are magnetic.



Signed by

Stephan J. Szyszkoski

Date

Sept. 17, 1997

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources - Forest Management Division