

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

**SURVEY &
 REMONUMENTATION**

MAY 22 1997

COMMISSION

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

For corners in ONTONAGON Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T 51N R 38W _____ E-9 _____
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

GERALD W. CARLSON, in a field survey on August 5 TH, 19 96, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 E-9: Section Corner common to Sections 20, 21, 28, and 29, T51N-R38W.
 1846: S.W. Higgins' and H. Higgins' original subdivision survey notes describe the corner monument as a wood post referenced by:
 12" Hemlock N45E 33 L
 12" Balsam S35W, 50 L

1966: A Government Monument Witness Record by C.C. Lindgren RLS #14098, for the Michigan State Highway Department, indicates the corner as a found 3/4" Iron Pipe at a fence corner and a found F.S. Location Poster. Referenced by:
 8" Tw. Y. Birch S75E, 07.90' 4" Maple S80W, 14.00'
 8" Tw. Y. Birch N25W, 14.15'
 No liber and page given.

Circa 1960 +/-: A Land Corner Record from Copper Range (Now Mead Paper) indicates the corner as a found 3/4" Iron Pipe at fence corner with a found F.S. Location Poster. Found references from August 1, 1966:
 8" Tw. Y. Birch S75E, 07.90' 4" Maple S80W, 14.00'
 8" Tw. Y. Birch N25W, 14.15'
 No liber and page given.
 Research on file with the Ontonagon County Remonumentation Representative.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 E-9: 1996: Found and accepted the 3/4" Iron Pipe as referenced above in Part "A" at corner of fences North, East, and South. This position checked well with stream calls South, 3.0 chains, North, 5.50 chains, and East, 22.50 chains. The Distance South is 5292.73', and the Distance East is 2635.29'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 E-9: 1996: Replaced found Iron Pipe with a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Ontonagon County Survey Monument stamped as follows to identify the corner: T51N., R38W., S. 20, S. 21, S. 28., S. 29.; 1996; P.S. 24589. Monument is 0.10' above ground. Measured existing references with d.h. nails in bottle caps and fd. B.T. Tags:
 10" Y. Birch N55E, 29.75' 8" Maple N88E, 55.28'
 Established references:
 14" Maple N64E, 56.56'
 Wooden Fence Corner Post S42W, 0.60' (To face)

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and B.T. Tags affixed. A fourth B.T. was unavailable, so we used the fence post shown above, which is very stable. Also found a white county survey marker sign attached to the fence corner post.
 Bk. 51-38, Pg. 57.

PEER GROUP APPROVED
Carl W. Carlson
 COUNTY REPRESENTATIVE 08-08-96

Signed by Gerald W. Carlson

Date 8-6-96

Surveyor's Michigan License No. 24589

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1972
 REVISED MAY 1973
 REVISED JAN. 1986
 REVISED OCT. 1995

