

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in ONTONAGON Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey T 51N R 38W \_\_\_\_\_ E-10  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

**SURVEY &  
 REMONUMENTATION**

MAY 22 1997

**COMMISSION**

Register of Deeds Stamp & File Number

GERALD W. CARLSON, in a field survey on August 5 TH, 19 96, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**  
 E-10: Quarter Corner common to Sections 28 and 29, T51N-R38W.  
 1846: S.W. Higgins' and H. Higgins' original subdivision survey notes describe the corner monument as a wood post referenced by:  
 12" Y. Birch N30E, 11 L  
 13" Hemlock S50W, 07 L  
 Research on file with the Ontonagon County Remonumentation Representative.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**  
 E-10: 1996: No evidence of original post or B.T.'s was found. The corner was established equidistant and on-line between the N.W. and S.W. Corners of Section 28. The 1992 R.A. Mick survey of Section 28 also established the corner using this method, although no monument was found to have been set by Mick at this location. The stream calls along the West Line of Section 28 fit fairly well. The distances North and South are 2646.72'. The corner is 56' +/- South and 75' +/- East of a corner of an electric fence running North and East.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**  
 E-10: 1996: Set a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Ontonagon County Survey Monument stamped as follows to identify the corner: T51N., R38 W., 1/4, S. 29, S. 28; 1996; P.S. 24589. Monument is 0.15' above ground.  
 Referenced by:  
 11" Y. Birch S50E, 14.56'                      9" Maple S80E, 32.42'  
 11" Maple S31W, 12.27'                      5" Y. Birch S87W, 34.19'  
 Green Steel Sign Post w/ Yellow Survey Marker Sign S34E, 1.95'  
 Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and B.T. Tags affixed.  
 Bk.51-38, Pg. 59.

PEER GROUP APPROVED  
*Gerald W. Carlsson*  
 COUNTY REPRESENTATIVE 08-08-96



Signed by Gerald W. Carlsson Date 8-6-96

Surveyor's Michigan License No. 24589