

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

JUDITH D. ROEHM
 Ontonagon County
 4/147 JDR Fee: 9.00
 08/13/96
 10:58
 Page 1 of 1

For corners in ONTONAGON (County) Located In: _____ Corner Code # _____

1. Public Land Survey T 51N R 38W _____ F-11
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

SURVEY &
 REMONUMENTATION

MAY 22 1997

COMMISSION

Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on August 1ST, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-11: Quarter Corner common to Sections 28 and 33, T51N-R38W.
 1846: S.W. Higgins' and H. Higgins' original subdivision survey notes describe the corner monument as a wood post referenced by:
 14" Elm N81W, 53 L
 12" Sugar S52E, 29 L

Circa 1960 +/-: A Land Corner Record from Copper Range (Now Mead Paper) indicates the corner as a 1 3/4" Iron Pipe. Corner is in a stand of second-growth hardwoods and Aspen, and the land slopes to the N.W.. Corner was referenced by:

20" Dry Hemlock S60W, 2' (Tree chopped out)
 8" Ironwood S85W, 11' (Put WAW mark on tree)
 6" Sugar S15W, 15' (Put names on tree)

No liber or page given.
 Research on file with the Ontonagon County Remonumentation Representative.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-11: 1996: Found and accepted a 1 1/2" I.D. Iron Pipe, 1.9' tall, as referenced in Part "A" above. Measured N70E, 1.35' to the corner fence post of a four-wire electric fence running North and East from corner. Cut lines on an aerial photograph of Section 28 indicate the N-S 1/4 Line and the South Section Line running North and East, respectively, from this corner position. The Distance West is 2636.18', the Distance North is 5515.62', and the Distance East is 2667.96'. This corner is also used in the 1992 R.A. Mick survey of Section 28.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-11: 1996: Replaced found 1 1/2" I.D. Iron Pipe with a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Ontonagon County Survey Monument, stamped as follows to identify the corner: T51N., R38W.; S. 28, S. 33, 1/4; 1996; P.S. 24589. Monument is 0.35' above ground. Established references:

4" Maple S72E, 22.56' 13" Maple S77W, 22.93'
 7" Maple N79W, 12.48' 8" Maple N13W, 18.24'
 Green Steel Sign Post w/ Yellow Survey Marker Sign S82E, 1.38'

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and B.T. Tags affixed.
 Bk. 51-38, Pg. 47.

PEER GROUP APPROVED

Earl W. Aspletary
 COUNTY REPRESENTATIVE

08-08-96



Signed by Gerald W. Carlson

Date 8-6-96

Surveyor's Michigan License No. 24589