

**SURVEY &
REMONUMENTATION**

DEC 16 1996

JUDITH D. ROEHN
Ontonagon County
LC 4/ 63 JEM Fee: 9.00
Page 1 of 1

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Ontonagon Located In: _____ Corner Code # _____
(County)

1. Public Land Survey Section 28 T 51N R 38W _____ G-11
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

Section corner to 27, 28, 33 and 34, T51N, R38W

I, John R. Garske, in a field survey on December 21, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2						
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Hiram Higgins, D.S. in 1847. He set a wood post from which an 8" maple bears - N60°E - 37 links and a 12" lynn - S40°W - 70 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a 1 1/2" I.D. iron pipe, setting 26" above the ground as shown on the 1992 survey by Robert Mick, RLS 16936. A metal forester's tag is on a dead 18" maple stub, due north, 8.0 feet. I monumented this corner location after checking into it from the 1/4 corner of Sections 27 and 28. This corner has been used and accepted for the survey of Section 28 and I am accepting the iron found as the best location for the corner position.

Research on file with the Ontonagon County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 2 1/2" dia. x 36" long aluminum pipe with a 3 1/4" dia. alum. cap stamped: T51N, R38W, S-28, S-27, S-33, S-34, 1995, RLS 28410 from which I established the following bearing trees and/or objects:

- 8" sugar - S23°E - 18.32 feet
- 8" sugar - N10°E - 22.20 feet
- 14" sugar - due west - 21.92 feet
- Steel sign post - N36°W - 1.50 feet

PEER GROUP APPROVED
Earl W. Applekamp
COUNTY REPRESENTATIVE 5-07-96



Signed by John R. Garske Date 4-16-96

Surveyor's Michigan License No. 28410

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983