


JUDITH D. POEHN  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970  
 Ontonagon County Remonumentation Corner

Ontonagon County  
 LC 5-146  
 Rec. Date 08-26-98 Time 13:39  
 RECORDATION FEE: 9.00

For corners in

Ontonagon County	Located in:	Corner Code #
1. Public Land Survey	T51N R38W	I-10
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No.	Recorded Plat	
5. Private Claims		



I, Joseph C. Domitrovich, in a field survey on August 18, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(I-10) 1/4 Corner Common to Sections 26 & 27, T51N, R38W

1846 - Hiram and Sylvester Higgins set a post.

12" Sugar S 34° E 55 links

10" Sugar N 25° W 30 links

1858 - Charles Merryweather, Surveyor, shows this corner on the Plat of the North 1/2 of Southwest 1/4 of Section 26, T51N, R38W (Plat on record at Ontonagon County Register of Deeds). There are no dimensions, but the Corner scales 377 feet West of the NW Corner of Lot 16.

1901 - Arthur W. Bates, Surveyor, shows the bearing of the Section line from the SW Corner of Section 26 as N 07°27' W on Plat of Dunstan and Hanchette's Addition to the Village of Maple Grove (Plat on record at Ontonagon County Register of Deeds). He does not indicate what is at this Corner or a distance to it.

1982 - Bruce Maki, Forester for Mead Corporation, stated that their Corner Records indicated a 1 1/4" iron pipe and yellow location poster at the Corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a 1 3/4" O.D. iron pipe at the Corner. I found the rotted remains of a Sugar Maple stumps at the location of both original B.T.s. The distance East to the NW Corner of Lot 16 (Plat of the North 1/2 of the Southwest 1/4 of Section 26) works well with scaled distance. The bearing from this pipe to the Southwest Corner of Section 26 works well with the Section line bearing from Dunstan and Hanchette's Addition Plat. A yellow Forest Service location poster faces this pipe. The tag is very rusty. The oldest readable date is 1978. This is the same pipe held as the 1/4 Corner by Mead Foresters. This pipe falls 205.53 feet West of a straight line between Section Corners. This is not inconsistent with work done by the original surveyors elsewhere in this Township. I accepted the pipe as the 1/4 Corner.

Research on file with County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 3/4" x 36" aluminum rod driven into the 1 1/4" O.D. iron pipe with a 3" diameter aluminum cap stamped to read: COUNTY REMONUMENTATION; S.26, S.27; 1/4; T.51N, R.38W; 1998; P.S. 37273. Corner falls 50 feet West of a fence line that meanders in a Northerly direction.

Witnesses:

4" Hard Maple	N 20° E	12.75'
4" Ironwood	S 70° E	1.30'
8" Ash	S 12° W	15.00'
Steel Sign Rail	West	1.19' (to face)
7" Hard Maple	N 69° W	9.26 (yellow F.S. poster)
NW Cor. Section 26	N 01°25'20" E	2703.05'
SW Cor. Section 26	S 07°28'18" E	2600.46'
NW Cor. Lot 16	N 82°08'05" E	374.73'

NOTE: Bearings to witness objects are magnetic. Distances are to a nail in side of the witness object unless noted.

Signed by Joseph C. Domitrovich

Date 8-19-98

Surveyor's Michigan License No. 37273

