

APR 25 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
ONTONAGON
(County)

Located In: Corner Code #

1. Public Land Survey	T 51 R 38	I-11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Recorded December 5 1994
at 2:05 o'clock P. M. in
Liber 3 page 229
Judith Markey
Register of Deeds

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Section Corner 27, 26, 35 & 34, T51N R38W

I, Earl W. Applekamp in a field survey on November 25, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Hiram Higgins, U.S. Deputy Surveyor.
Set Wood Post.

Original Bearing Trees:

Hemlock 12" S22°E 70 Links (46.20')
Maple 14" N60°W 25 Links (16.50')

ONTONAGON COUNTY
PEER APPROVED

EW Applekamp
Dist Co Rep
11-30-94

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

At the corner position I found a 1½" pipe with stones & concrete encircling it. This corner was used for the starting point of the plat of the village of the village of Maple Grove in Greenland in 1855. Jeffs addition to the village of Maple Grove used the corner in 1901. Two other plats also used this corner. I personally used the corner for a survey performed in 1978 and later for locating lots in the plats.

Research on file with County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 1"x26" aluminum rod with a 3¼" cap on it into the 1½" pipe. Top of the cap is 1" below the surface of ground. Cap is stamped to read, County Remonumentation: S27, S26, S35, S34, T51N R38W, 1994, P.S. 17610. I tied the corner to the following trees and reference objects

Power Pole N12°W 65.15' - Power Pole N63°E 81.10'
Spruce 18" S79°W 28.50' - Steel Stop Sign N69°E 4.68'



Signed by Earl W. Applekamp Date November 29, 1994
Surveyor's Michigan License No. 17610