

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ontonagon Located In: Corner Code #
 (County)

1. Public Land Survey T 51N R 38W L-13
 T ___ R ___
 T ___ R ___
 T ___ R ___

2. Property Controlling S ___ T ___ R ___
 in Section S ___ T ___ R ___

3. Miscellaneous S ___ T ___ R ___
 Property in Sec. S ___ T ___ R ___

**SURVEY &
 REMONUMENTATION**

APR 07 1998

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Joseph C. Domitrovich, in a field survey on October 7, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

(L-13) S 1/4 Corner Section 36, T 51N, R 38W, on the 5th Correction Line

A. Description of original monument and accessories and/or subsequent restoration:

1845 - Austin Burt set 1/4 post
 8" Maple N 45° E 23 links
 10" Fir N 30° W 34 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found no remains of original corner or accessories. Corner now falls in the clearing for a NE-SW Powerline. An old road bed runs E-W across the 1/4 corner position.

I re-established the corner midway between section corners to East and West but held old road bed for the North-South position. This works well with GLO distances to section corners East and West:

SW Cor. Section 36 N 89° 19' 28" W 2646.06'
 SE Cor. Section 36 N 89° 52' 22" E 2646.06'
 C.C. Sections 4 & 5, T50N, R38W N 89° 19' 28" W 923.52'

PEER GROUP APPROVED

Earl W. Applbaum
 COURT 12-01-97

Research on file with County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 5/8" x 24" rebar with a 3" diameter aluminum cap stamped to read: COUNTY REMONUMENTATION; S.C.; 1/4; S. 36; T. 51N, R. 38W; 1997; P.S. 37273. The corner falls 14.4' Northwesterly of Westerly line of power poles.

Witnesses:

10" Twin Soft Maple N 20° E 38.55'
 Steel Sign Post South 0.73' (to face)
 7" Balsam S 87° W 42.80'
 4" Soft Maple N 26° W 31.35'

NOTE: Bearings are magnetic. Distances are to nail in side of witness objects unless noted.

Signed by John C. Domitrovich
 Surveyor's Michigan License No. 37273

Date 11/25/97

