

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 of 1
Ontonagon County Remonumentation Corner

Ontonagon County LC 54 141
Rec. Date 08/26/98 Time 13:29
RECORDING FEE: 9.00

For corners in

Table with columns: Ontonagon County, Located in:, Corner Code #. Rows include Public Land Survey (T51N R37N, T51N R38W, T R, T R, T R), Property Controlling in Section (S, S, S, S), Miscellaneous Property in Sec. (S, T, R, R), Lot No., Recorded Plat, Private Claims.

Register of Deeds Stamp & File Number. Includes a grid for recording and a date stamp: AUG 26 1998.

I, Joseph C. Domitrovich, in a field survey on August 12, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid for recording with columns A-M and rows 1-13. Row 10, Column A contains a dot.

A. Description of original monument and accessories and/or subsequent restoration:

(A-10) 1/4 Corner Common to Section 25, T51N, R38W & Section 30, T51N, R37W

- 1845 - Austin Burt set a post. 10" Sugar S 25° W 18 links (11.88'). 12" Hemlock N 52° W 34 links (22.44'). 1976 - Keith Sackett, P.S. 19006, for Michigan DNR, found a 1" I.D. iron pipe and also a hemlock log with scribing— possible original bearing tree. He established three N.B.T.s: 14" Y. Birch N 10° W 28.8', 12" Sugar S 25° E 21.8', 22" Sugar S 22° W 13.0'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

At the corner I found the pipe as called for by Sackett and the rotted remains of a fallen 14-16" Hemlock at the position of the original Hemlock B.T. I found all three of Sackett's N.B.T.s. His 22" Sugar N.B.T. falls at the position of Austin Burt's original B.T. and could very possibly be the same tree. The distance South to the Southeast Corner and distance North to the Northeast Corner work well with GLO.

I accepted the pipe as the corner and have monumented it as such.

Research on file with County Remonumentation Representative.

FREE GROUP APPROVED
Paul W. Applekamp
COUNTY REMONUMENTATION
8-19-98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 3/4" x 36" aluminum rod driven inside the 1 1/4" O.D. pipe, with a 3" diameter aluminum cap stamped to read: COUNTY REMONUMENTATION; S.25, S.30; 1/4; T.51N, R.38W, R.37W; 1998; P.S. 37273.

Witnesses table with columns: Witness, Bearing, Distance, Notes. Includes 18" Twin H. Maple, 14" H. Maple, 24" H. Maple, 16" Y. Birch, Steel Sign Rail, NE Cor. Section 25, SE Cor. Section 25.

NOTE: Bearings to witness objects are magnetic. Distances are to a nail in side of the witness object unless noted.

Signed by [Signature] Date 8-19-98

Surveyor's Michigan License No. 37273