LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Ontonagon (County)

	Located In:			Corner Code #
1. Public Land Survey		T____	R____	
		T____	R____	
		T____	R____	
	S____	T____	R____	
2. Property Controlling	S 36	T 51N	R 38W	11
in Section	S 36	T 51N	R 38W	12
3. Miscellaneous	S____	T____	R____	
Property in Sec.	S____	T____	R____	

Register of Deeds Stamp & File Number

4. Lot No. _____ , Recorded Plat_____

5. Private Claims

12 Feb 01 2007
11 Jan 24 2007



I, Stephan J. Szyszkoski, in a field survey on _____, 20 ____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(11-Sec. 36) Southwest 1/16 corner, Section 36. Not established in the original survey.
(12-Sec. 36) South 1/16 corner, Section 36. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(11-Sec. 36) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.
(12-Sec. 36) Established the corner midway and on a straight line between Quarter corner 1335.16' south and the intersection of 1/4 lines of Sec. 36 1335.16' north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(11) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
7" Sugar S83E 15.6' mrkd "1/16 BT"
9" Sugar S27W 10.7' do
15" Hemlock S82W 26.3' do
8" Maple N50W 11.1' do
Sq'd a forked Ironwood S82W 4.7' from corner (no nail set). Bearings are magnetic. Distances are to nail with tag.

(12) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
8" Sugar East 2.8' mrkd "1/16S BT"
8" Sugar S05W 16.3' do
8" Y.Birch S27W 23.2' do
6" Sugar N50W 5.7' do
Set sq'd spruce post adjacent. Bearings are magnetic. Distances are to nail with tag.

STATE OF MICHIGAN
STEPHAN J. SZYSZKOSKI
LAND SURVEYOR
No. 33986
LICENSED LAND SURVEYOR

Signed by Stephan J. Szyszkoski Date 2/7/2007

Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
Revised May 14, 1975
Revised Jan., 1983
Rervised Oct., 1995