

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Ontonagon
 (County)

Located In:

Corner Code #

- | | | | | | |
|---------------------------------------|---|-------|---|-------|----------------|
| 1. Public Land Survey | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | R |
| | S | 36 | T | 51N | R 38W |
| | S | 36 | T | 51N | R 38W |
| | | | | | W-E 1/64 25/36 |
| | | | | | 15 |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |
| 4. Lot No. _____, Recorded Plat _____ | | | | | |
| 5. Private Claims | | | | | |

Register of Deeds Stamp & File Number

Jan 24 2007

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (W-E 1/64 25/36) W-E 1/64 corner between Sections 25 and 36, being the NE corner of the NW 1/4 of the NW1/4 of the NE 1/4 of Section 36. Not established in the original survey.
- (15-Sec. 36) West 1/16 corner on the south line of Section 36. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (W-E 1/64 25/36) Established the corner midway and on the Section line between Quarter corner of record 685.03' West and 1/16 corner # 2 position 685.03' East. The position for the corner falls in the west-bound lane of State Highway M-26 and was not monumented. Established a Witness Corner on the 1/64 line 40.00' south of the corner position.
- (15-Sec. 36) Established the corner midway and on the Correction Line between monumented Section and Quarter corners of record 1323.04' west and east. The position for the corner falls in the N. edge of an E-W gravel road, west of Hwy. M-26.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|--|
| (W-E 1/64) Set 1"IDx32" I.pipe with 4" alum. MDNR cap on the N-S 1/64 line, 40.00' south of the corner position. | (15) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: |
| Set measuring nails in: | 3" Sugar S47W 40.6' mrkd "1/16S BT" |
| Hwy sign post N23E 77.4' nail/tag | 8" Maple N71W 42.0' do |
| 4" Balsam S50E 38.5' mrkd "WC BT" | 8" Maple N33W 32.8' do |
| 9" Ash S18W 36.7' do | metal sign post N54W 18.3' no nail/tag |
| 8" Ash S83W 34.6' do | Paint stripe W. edge M-26 15' east. |
| Sq'd ash post adjacent. Bearings are magnetic. Distances are to nail with tag. | Bearings are magnetic. Distances to trees are to nail with tag. |



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 2/7/2007

For the Michigan Department of Natural Resources, Office of Land and Facilities