

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 51 N.R. 39-40 W


Ontonagon COUNTY

DESCRIPTION OF CORNER Section Corner common to Secs. 18-19-13-24

CORNER MONUMENT 3/4" Iron Pipe

DATE MONUMENT PLACED AND WITNESSED 6/7/1966

WITNESSES TO CORNER..... 20" Hard Maple (S19 NBT), S 41° E, 37 lks.



10" Hard Maple (S24 NBT), S 87° W, 85 lks.

14" Hard Maple (S13 NBT), N 22° W, 67 1/2 lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner re-witnessed as placed by unknown persons. Found 3/4" Iron Pipe with a 30" Hard Maple Bearing N 67° W, 25 lks. Tree is green and has a large rotted hole at proper height for witness mark.

Also found a 1/2" Iron Pipe bearing N 33° W, 38 lks.

Corner lies 1 chain South of old Log road and 3/4 chain North of foot of hill.

SURVEYOR'S SEAL

Billy D. Buckler
SIGNED Billy D. Buckler DATE 8/12/1966
REGISTERED LAND SURVEYOR