

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>51</u> N. <u>X</u> , R. <u>39</u> K. <u>W.</u>	<u>C13, B13, A13</u>
2. PROPERTY CONTROLL- ING IN SECTION_____	<u>31</u> , T. <u>51</u> N. <u>X</u> , R. <u>39</u> K. <u>W.</u>	<u>16</u>
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. _____, R. _____ E. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on See below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

Corner C-13: Original monument and accessories not found. Found old Forest Service location poster dated 6-24-46. Found old blazed lines north - east - west. Also found remains of old post.'

Corner B-13: Original monument and accessories not found.

Corner A-13: Original monument and accessories not found.

Corner 16: Not set on original survey nor subsequently apparently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

Corner C-13: Re-established 8-17-76 at old post location.

Corner B-13: Re-established 11-1-76 on line between section corners east and west.

Corner A-13: Re-established 8-26-76 on line between section corners.

Corner 16: Established 11-1-76 on line between section corner east and one-quarter corner west.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Corner C-13: Set 1" I.D. x 36" I.P. w/4" aluminum cap. Corner falls 10 ft. west of old N-S logging road.

16" Hemlock N10°E 19 ft. S32, NBT  
6" Y.Birch S15°W 32.8 ft. S 3, NBT  
5" Y.Birch S17°E 57.8 ft. S 3, NBT

Corner 16: Set 1" I.D. x 36" I.P. w/4" aluminum cap.

6" Sugar S88°E 6.2 ft. 1/16S,BT  
4" Maple N32°E 10.4 ft. 1/16S,BT  
8" Sugar N43°W 9.3 ft. 1/16S,BT

Corner B-13: Set 1" I.D. x 36" I.P. w/4" aluminum cap.

7" Maple S59°W 8.0 ft. 1/4S, NBT  
4" Sugar N37°E 10.3 ft. 1/4S, NBT  
5" Sugar N37°W 18.0 ft. 1/4S, NBT  
5" Sugar squared N77°E 4.1 ft. marked 1/4S and 31

Corner A-13: Set 1" I.D. x 36" I.P. w/4" alum. cap.

8" Elm N05°W 27.5 ft. S36, NBT  
4" Sugar N69°E 12.5 ft. S31, NBT  
6" Maple S22°W 29.0 ft. S 4, NBT

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY Michael W. Roose Michael W. Roose DATE 12-28-76  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY Keith L. Sackett DATE Dec. 28, 1976  
MICHIGAN REGISTERED LAND SURVEYOR  
Keith L. Sackett

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

