

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
T **Ontonagon**
County

	Located In:	Corner Code #1
1 Public Land Survey	T 51N R 39W	B9
	T R	B11
	T R	C9
	T R	C11
2 Property Controlling in Section	S T R	
3 Miscellaneous Property in Sec.	S T R	

Register of Deeds Stamp & File Number

4 Lot No. _____, Recorded Plat _____
5 Private Claims _____

I, **Keith Sackett**, in a field survey on **January 3**, 19 **90**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	15	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A Description of original monument and accessories and/or subsequent restoration:

B9	B11	C9	C11
Original monument and accessories not found.	Original monument and accessories not found.	Original monument and accessories not found.	Original monument and accessories not found.

B Description of corner evidence found and/or method applied in restoring or reestablishing corner.

B9	B11	C9	C11
Restored by proportion.	Restored by proportion distance.	Restored by double proportion distance.	Restored by double proportion distance.

C Description of monument for corner and accessories established to perpetuate locating the position of the corner.

B9	B11	C9	C11
Set 1" ID x 32" iron pipe w/4" aluminum cap. 6" sugar N65W 5.0' 1/4s, NBT 3" yellow birch S65E 7.1' 1/4s, NBT 3" sugar N55E 14.2' 1/4s, NBT	Set 1" ID x 32" iron pipe w/4" aluminum cap. 5" sugar S86E 10.7' 1/4s, NBT 7" sugar N45W 8.5' 1/4s, NBT 4" maple S65W 26.0' 1/4s, NBT	Set 1" ID x 32" iron pipe w/4" aluminum cap. 7" cedar S85E 26.1' s29, NBT 6" maple S45W 0.8' s30, NBT 4" sugar S06E 6.6' s29, NBT	Set 1" ID x 32" iron pipe w/4" aluminum cap. 3" ash S70E 4.4' s32, NBT 7" poplar S85W 12.4' s31, NBT 2" maple N55E 8.8' s29, NBT

Signed by Keith Sackett Date August 27, 1990

Surveyor's Michigan License No. _____

19006