

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
T Ontonagon
 (County)

	Located In:	Corner Code -##
1 Public Land Survey	T 51N R 39W	C10
	T R	
	T R	
	T R	
2 Property Controlling in Section	S 30 T R	2
	S T R	7
3 Miscellaneous Property in Sec	S T R	16
	S T R	

Register of Deeds Stamp & File Number

4 Lot No. _____, Recorded Plat _____
 5 Private Claims _____

I, Keith Sackett, in a field survey on January 10, 1990, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A Description of original monument and accessories and/or subsequent restoration:

C10	2	7	16
Original monument and accessories not found.	Not set on original survey nor subsequently, apparently.	Not set on original survey nor subsequently, apparently.	Not set on original survey nor subsequently, apparently.

B Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C10	2	7	16
Restored midway and on line.	Established midway and on line.	Established midway and on line.	Established midway and on line.

C Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C10	2	7	16
Set 1" ID x 32" iron pipe w/4" aluminum cap.	Set 1" ID x 32" iron pipe w/4" aluminum cap.	Set 1" ID x 32" iron pipe w/4" aluminum cap.	Set 1" ID x 32" iron pipe w/4" aluminum cap.
4" ash N80W 11.6' 1/4s NBT	4" maple S80E 8.2' 1/16s, BT	9" cedar N50E 34.6' 1/16s, BT	4" maple N38E 8.0' 1/16s, BT
5" twin ash S28W 7.9' 1/4s NBT	3" maple S74W 14.9' 1/16s, BT	4" yellow birch S45W 17.3' 1/16s, BT	6" maple N50W 2.9' 1/16s, BT
7" ash S86E 35.1' 1/4s NBT	4" maple N60W 24.6' 1/16s, BT	7" ash N10W 42.0' 1/16s BT	4" maple S04W 9.4' 1/16s, BT
			4" ash squared west 3.4'

Signed by

Keith Sackett

Date

August 27, 1990

Surveyor's Michigan License No

19006