

REMONUMENTATION

APR 29 1996

COMMISSION

JUDITH D. ROEHM 12/18/95
Ontonagon County 15:00
LC 4/ 6 JEM Fee: 9.00
Page 1 of 1

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in ONTONAGON (County) Located In: Corner Code #
1. Public Land Survey T 51N R 39W A-2
T 51N R 40W M-2
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

1/4 Corner common to Section 1 & 6, T51N, R39 & 40W.

I, Earl W. Applekamp, in a field survey on November 6, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Corner established by William Burt, U.S. Deputy Surveyor, August 1845. Set Post.

ORIGINAL BEARING TREES:

Hemlock 14" S50°W 12 links (7.92 feet)
Hemlock 18" N63°E 17 links (11.22 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. An old fence line runs North from this location. A well maintained dirt road runs East from this location and is used as the occupation line. Testimony from Jerry Koski, a former U.S. Forest Service employee, Survey Technician for 26 years said he had used this location as the 1/4 corner.

Research on file.

PEER GROUPE APPROVED

Earl W Applekamp 12-14-95
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 1/2"x30" aluminum pipe with a 3/4" cap stamped to read: COUNTY REMONUMENTATION, T51N, R39W, R40W, S.1, S.6, 1/4, 1995, P.S. 17610. I established the following bearing trees and reference objects:

8" Maple S06°W 19.36 feet - 10" Maple N76°E 78.51 feet
8" Maple N41°W 81.67 feet - Steel Sign Post, North 7.20 feet
N60°E 36 feet to centerline of Power Line



Signed by Earl W Applekamp
Surveyor's Michigan License No. 17610

Date November 11, 1995

L