

SURVEY & REMONUMENTATION

APR 29 1996

JUDITH D. ROEHM
 Ontonagon County
 LC 4/ 7 JEM Fee: 9.00
 Page 1 of 1

COMMISSION LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in ONTONAGON Located In: _____ Corner Code # _____
 (County)

- 1. Public Land Survey T 51 R 39 B-3
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Section S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

$\frac{1}{4}$ Corner common to Sections 6 & 7, T51N R39W.

I, Earl W. Applekamp, in a field survey on August 07, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, U.S. Deputy Surveyor, August 1845. Set Maple Post.

ORIGINAL BEARING TREES:

Hemlock 14" S74°E 23 links (15.18 feet)
 Hemlock 8" N48°W 35 links (23.10 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. Michigan highway plans produced in 1948 show a 4" wooden hub as the $\frac{1}{4}$ Corner with ties. I was able to find one of the ties, a White birch. There is an old fence running N - S. Two of these ties were to fence posts N & S. Fence posts were on the ground. At the corner position there was a large Cedar Post in fair condition. The remains of a fence line was running East from this position. I checked the distance from the $\frac{1}{4}$ Corner to the centerline of U.S.-45, it agreed with the distance shown on the Highway drawings. I accepted the position and monumented the corner as described in "C" below.

Research on file.

PEER GROUP APPROVED

Earl W. Applekamp 12-14-95
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 $\frac{1}{2}$ "x30" aluminum pipe with a 3 $\frac{1}{4}$ " cap stamped to read: COUNTY REMONUMENTATION, T51N R39W, $\frac{1}{4}$, S6, S7, 1995, P.S. 17610. I established the following bearing trees and sign post:

6" Aspen N74°W 89.21 feet - 4" Elm S09°E 66.83 feet
 4" W. Birch S56°E 12.66 feet - Steel Sign Post South 1.85 feet



Signed by *Earl W. Applekamp*
 Surveyor's Michigan License No. 17610

Date September 21, 1995

7