

SURVEY & REMONUMENTATION

APR 29 1996

JUDITH D. ROEHM
 Ontonagon County
 LC 4/ 9 JEN Fee: 9.00
 Page 1 of 1

COMMISSION LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in	Located In:	Corner Code #
ONTONAGON (County)		
1. Public Land Survey	T <u>51</u> R <u>39</u>	<u>C-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Section	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

$\frac{1}{4}$ Corner common to Section 5 & Section 6, T51N R39W.

I, Earl W. Applekamp, in a field survey on August 16, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, U.S. Deputy Surveyor, August 1845. Set Maple Post.

ORIGINAL BEARING TREES:

Hemlock 14" S74°E 23 links (15.18 feet)
 Hemlock 8" N48°W 35 links (23.10 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. Corner was established by single proportionate measurement from opposite section corners North & South. At this position there was a clear cut line running East. A barb wire fence ran North and South through this location. There was a tree blazed a few feet from the corner position.

Research on file.

PEER GROUP APPROVED

Earl W. Applekamp 12-14-95
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 $\frac{1}{2}$ "x30" aluminum pipe with a 3 $\frac{1}{4}$ " cap stamped to read: COUNTY REMONUMENTATION, T51N R39W, S.5, S.6, 1995, P.S. 17610. I established the following bearing trees and reference objects:

6" Maple S39°W 14.13 feet - 7" Maple N42°W 21.64 feet
 8" Maple N56°E 20.95 feet - Steel Sign Post, North 2.12 feet



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date October 06, 1995