

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ontonagon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>51N</u> R <u>39W</u>	<u>D-7</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

JEM

OCT 3 01997

COMMISSION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Joseph C. Domitrovich, in a field survey on April 21, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

(D-7) 1/4 Corner Sections 17 and 20, T51N, R39W

A. Description of original monument and accessories and/or subsequent restoration:

1846 - Austin Burt, set B. Ash Post
 10" Sugar S 44° E 44 links
 12" B. Ash N 48° W 27 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found no remains of the original corner or accessories. At the corner I found an East-West paved road, a gravel road to the south and an old fallen fence to the North. At the intersection of the centerlines east, west and south and fence line north I detected a deep magnetic reading. This position works well with GLO distances to section corners east and west. I accepted this position as the 1/4 corner and monumented it as such.

PEER GROUP REPRESENTATIVE
Paul W. [Signature] 5-12-97
 COUNTY REPRESENTATIVE

Research on file with County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 5/8" x 24" rebar with a 3" diameter aluminum cap stamped to read: County Remonumentation; T51N, R39W; 1/4 S.17, S. 20; 1997; P.S. 37273. I also placed a reference monument (R.M.) to the North consisting of a 2" x 30" aluminum pipe with a 3" aluminum cap stamped to indicate that the corner is south 33.28'

Witnesses

R.M.	North	33.28'
Power Pole	S 03° W	173.88'
SE Garage Fdn. Cor.	N 51° W	68.98'
Power Pole	N 07° W	179.69'
NE Cor. Sec. 20	East	2644.21' (2644.62' GLO)
NW Cor. Sec. 20	S 89° 50' 56" W	2645.30' (2644.62' GLO)

NOTE: Bearings are magnetic. Distances are to nail in side of witness objects unless noted.

Signed by Joseph C. Domitrovich
 Surveyor's Michigan License No. 37273

Date 5/12/97

