

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Ontonagon County Remonumentation Corner

Ontonagon County

Page 1 of 1 LC 5/210
REC. Date 07/27/99 Time 14:58
RECORDING FEE: 9.00

For corners in

Table with columns: Ontonagon County, Located in:, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec., Lot No., and Private Claims.

SURVEY & REMONUMENTATION
MAR 23 2000
SECTION

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column D and row 2.

I, Joseph C. Domitrovich, in a field survey on July 15, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E-2) 1/4 Corner Common to Sections 4 and 5, T51N, R39W

1845 - Austin Burt used an 11" Fir for the 1/4 corner
7" Hemlock S10°W 28 links
6" Sugar N37°E 34 links

PEER GROUP APPROVED
Earl W Applekamp 7-20-99
COUNTY REPRESENTATIVE

1985 - Earl Applekamp, in a survey recorded in Liber 1 of Surveys, page 79, shows a 5/8" iron pin at this corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found no remains of the original corner or accessories. Earl Applekamp's 5/8" pin has been obliterated by Woodspur Road reconstruction. I works well with occupation and with Section Corners North and South. I accepted and monumented this position. recreated the position of his pin using recovered Right-of-Way corners and distances shown on his survey. This position

Research on file with County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 5/8" iron pin with a 3" diameter brass cap stamped to read: COUNTY REMONUMENTATION; T.51N, R.39W; 1/4; S.4, S.5; 1999; P.S. 37273. Corner falls 2' east of centerline of Woodspur Road. I also established a Reference Monument (R.M.) to the east; a 2 1/2" x 30" aluminum pipe with a 3" diameter aluminum cap stamped to indicate that the 1/4 corner is N86°18'W 25.47'. Ties:

Table listing witness objects and their bearings/distances: Power Pole (S18°E 97.30'), 7" Spruce (S79°W 29.62'), 5" White Birch (N34°W 53.17'), R.M. (S86°17'36"E 25.47'), NE Corner of Sec. 5 (N00°14'18"W 2603.73' (2603.7 GLO)), SE Corner of Sec. 5 (S00°13'18"E 2640.00')

NOTE: Bearings to witness objects are magnetic. Distances are to a nail in side of the witness object unless noted.

Signed by [Signature]

Date 7/20/99

Surveyor's Michigan License No. 37273

