

**SURVEY & REMONUMENTATION**

APR 29 1996

COMMISSION

JUDITH D. ROEHL  
 Ontonagon County  
 LC 3/404 JEM Fee: 9.00  
 Page 1 of 1

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in Ontonagon Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey T 51N R 39W F-1  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Joseph C. Domitrovich, in a field survey on October 5, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

North 1/4 Corner Section 4, T51N, R39W

Corner was not set in original survey, but was established midway between closing corners which would place it 80 links (52.80') east of the South 1/4 Corner of Section 33, T52N, R39W.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found an old east-west fenceline at the north side of a cleared field. A new fenceline fell just to the south of it. Found no other evidence of corner position.

Established corner position at 52.80' east of the South 1/4 Corner, Section 33, T52N, R39W, and on line between it and the standard corner to the east. This places the corner on the old east-west fenceline.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Corner is an aluminum pipe with a 3" diameter stamped aluminum cap and falls on an old east-west fenceline at the north side of a field and the south side of a Red Pine plantation.

**Witnesses:**

- 10" Red Pine N 40° W 5.53'
- Sign Post North 1.14'
- 7" Red Pine N 20° E 5.40'
- 36" Twin Soft Maple N 43° E 16.00'

**PEER GROUP APPROVAL**  
*Earl Appelkamp*  
 COUNTY REPRESENTATIVE 11-06-95

South 1/4 Corner Section 33,, T52N R39W (Stamped Monument) West 52.80'



**NOTE:** Bearings are magnetic. Distances are to nail in side of witness objects unless noted.

Signed by J. C. Domitrovich Date 10/18/95  
 Surveyor's Michigan License No. 37273