

SURVEY & REMONUMENTATION

APR 29 1996

COMMISSION

JUDITH D. ROEHM
Ontonagon County
LC 3/ 332 JEM Feet 9.00
10/19/95
13:20
Page 1 of 1

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in <u>Ontonagon</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>51N</u> R <u>39W</u>	<u>G-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

*
NO

I, Joseph C. Domitrovich, in a field survey on October 18, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Closing Section Corner Sections 4 and 3 T51N, R39W

1845 -William A. Burt, intersected north boundary 40 links (26.40') east of post and set post
 20" Hemlock S 35° W 30 links (19.80')
 6" Sugar N 29° E 31 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a 3/4" square end twisted iron at the standard section corner, Sections 33 and 34, T52N, R39W. (Now a county monument.) Re-established closing corner at GLO distance (26.40') east of standard corner, and on line with section corners to west. At S 35° W 19.80' there now is a large dirt mound from a very large wind thrown tree (unable to determine species), possibly the 20" Hemlock Bearing tree.

Placed county monument at corner position.

(Research on file with County Remonumentation Representative.)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


Corner is an aluminum pipe with a 3" diameter stamped aluminum cap.

Witnesses:

4" Hemlock	N 40° E	4.95'
10" Ash	S 80° E	6.38'
8" Soft Maple	S 53° W	13.10'

Standard Section Corner, Sections 33 and 34, T52N, R39W
 (Aluminum pipe with 3" diameter stamped aluminum cap) West 26.40'
 Sign Post North 0.94'

PEER GROUP APPROVED
Paul W. Applekamp
 COUNTY REPRESENTATIVE



NOTE: Bearings are magnetic. Distances are to nail in side of witness objects unless noted.

Signed by Joseph C. Domitrovich Date 10/18/95
 Surveyor's Michigan License No. 37273