

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1979

ROBERT D. DOMITROVICH

1P

Ontonagon County

11-5-2000

12-21-1999

1112006

1112006

1112006

For corners in

Ontonagon County	Located in:	Corner Code #
1. Public Land Survey	T51N R39W	G-3
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	
4. Lot No.	Recorded Plat	
5. Private Claims		

SURVEY & REMONUMENTATION

MAR 23 2000

SECTION

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M	N
1														
2														
3														
4														
5														
6														
7														
8														
9														
10														
11														
12														
13														

I, Joseph C. Domitrovich, in a field survey on December 1, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1979, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereto as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 (G-3) Corner common to Sections 9, 4, 9, & 10, T51N, R39W

1946 Armin Hunt set a Range Post with ties
 14" Birch S 20°W 27 links
 14" Birch N 63°E 22 links

1951 Mead Corporation Land Corner records call for a 1" iron bar at fence corner.

1960 C.C. Lindgren RLS 14098 (for Michigan State Highway Department) shows this corner on Government witness record card. He shows distances to Section Corners one mile east and west and to 1/4 corner 1/2 mile north.

1993 Mead Corporation Land Records call for a 1" solid iron pipe at a fence corner in a beaver dam. Ties
 14" White Ash S 50°E 5'
 6" White Ash N 04°W 0'
 12" Balsam N 80°E 20'
 6" White Ash N 86°W 20'

DAVE GROUP APPROVAL
 12-20-99

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 I found no remains of the original corner or accessories. I recovered the 1" iron pin called for by Mead and their 4 witnesses. Distances to section corners east and west are in agreement with those called for by Lindgren. Distances also work well with GLO. I accepted the iron pin as the section corner.

Research on file with County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Corner is a 1/2" x 48" aluminum rod with a 3" diameter aluminum cap stamped to read: COUNTY REMONUMENTATION, T51N, R39W; S. 3, S. 4, S. 9, S. 10; 1999; P.S. 37273. Ties:

7" Ash	N 07°W	0.57'	(existing blaze)
6" Ash	West	22.35'	(existing blaze)
10" Soft Maple	S 10°W	24.37'	(existing blaze)
Steel Sign Rail	South	0.04'	(in face)
14" Ash	S 55°E	5.76'	(existing blaze)
SW Corner Section 4	S 89°39'54"W	5282.88' (meas.)	5282.84' (Lindgren) 5282.84' (GLO)
SE Corner Section 3	N 89°51'28"E	5273.66' (meas.)	5274.39' (Lindgren) 5277.36' (GLO)
E 1/4 Corner Section 4	N 01°00'13"W	2638.44' (meas.)	2640.48' (Lindgren) 2640' (GLO)

NOTE: Bearings to witness objects are magnetic. Distances are to a nail in side of the witness object unless noted.

Signed by Joseph C. Domitrovich

Date 12/14/99

Surveyor's Michigan License No. 37273

