

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ontonagon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>51</u> N R <u>39</u> W	<u>I-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

SURVEY & REMONUMENTATION

APR 07 1998

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Joseph C. Domitrovich, in a field survey on November 21, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

(I-13) Corner Common to Sections 34 & 35, T51N, R39W

A. Description of original monument and accessories and/or subsequent restoration:

1845 - Austin Burt set post

30" Hemlock N 60° E 29 links
 6" Lynn N 52° W 49 links

1947 - Michigan State Highway Department (M.S.H.D.), for U.S. Highway 45 plans, shows the corner and distance North to the West 1/4 corner of Section 35, as well as a distance East to the Closing corner Sections 5 & 4, T50N, R39W. There is no description of this corner, but the description of the Closing corner of Sections 6 & 5, which falls in a field, is 1" gas pipe.

Ties: 5" Maple N 30° W 2.36'
 2" Maple S 52° W 23.13'
 10" Hemlock S 30° E 7.38'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a 1" iron pipe at this corner. This pipe matches the description and ties listed for the Closing Corner of Sections 5 & 6, T50N, R39W, above. From this pipe, a mound from the windthrown roots of a very large tree matches the bearing and distance to GLO 30" Hemlock. Distance East to the Closing Corner of Sections 5 & 4, T50N, R39W works well with M.S.H.D. (7339.78' - M.S.H.D., 7352.4 - GLO, 7340.19' - Meas.), as well as the distance North to the 1" pipe called the West 1/4 corner by the M.S.H.D. (2595.97' - M.S.H.D., 2595.04' - Meas.).

I accepted this pipe as the Section Corner.

PEER GROUP APPROVAL
Carl W Applekamp
 12-01-97

Research on file with County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 2" x 30" aluminum pipe with a 3" diameter aluminum cap, placed over a 1" pipe, stamped to read: COUNTY REMONUMENTATION; T.51N, R.39W; S. 34, S. 35; S.C.; 1997; P.S. 37273.

Witnesses:

14" Soft Maple	S 37° W	23.08'	(2" Maple M.S.H.D.)
12" Soft Maple	N 50° W	2.47'	(5" Maple M.S.H.D.)
4" Soft Maple	N 22° E	9.68'	
14" Hemlock	S 40° E	7.43'	(10" Hemlock M.S.H.D.)
Steel Sign Post	South	1.01'	(to face)
W 1/4 Cor. Section 35 (per M.S.H.D.)	N 00° 08' 12" W	2595.04'	
S 1/4 Cor. Section 35	N 89° 50' 53" E	2630.82'	

NOTE: Bearings are magnetic. Distances are to nail in side of witness objects unless noted.

Signed by J. C. Domitrovich Date 11/30/97
 Surveyor's Michigan License No. 37273

