

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ontonagon Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T 51N R 39W J-13
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

**SURVEY &
 REMONUMENTATION**

APR 07 1998

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Joseph C. Domitrovich, in a field survey on November 21, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

(J-13) South 1/4 Corner of Section 35, T51N, R39W

A. Description of original monument and accessories and/or subsequent restoration:

1845 - Austin Burt set post
 20" Birch N 71° E 34 links
 12" Birch N 12° W 25 links

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

PEER GROUP APPROVED
Carl W. Appelkamp
 COUNTY SURVEYOR 12-01-97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

The original corner and accessories were not recovered. The only evidence of occupation was a fenceline strung from tree to tree in a Northerly direction.

I re-established this corner by single proportionate measurement. This corner works reasonably well with the fence to the North.

Research on file with County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 2" x 30" aluminum pipe with a 3" diameter aluminum cap stamped to read: COUNTY REMONUMENTATION; 1/4; S. 35; T.51N, R.39W; S.C.; 1997; P.S. 37273.

Witnesses:

6" Hard Maple West 34.22'
 8" Hard Maple N 02° W 17.13'
 3" Ironwood S 86° E 14.61'
 6" Hard Maple S 25° E 18.58'
 Steel Sign Post South 1.26' (to face)
 SW Cor. Section 35 S 89° 50' 53" W 2630.82'
 SE Cor. Section 35 N 89° 50' 53" E 2630.82'

NOTE: Bearings are magnetic. Distances are to nail in side of witness objects unless noted.

Signed by J. C. Domitrovich

Date 11/30/97

Surveyor's Michigan License No. 37273

