

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>51</u> N. <u>8</u> , R. <u>40</u> E. <u>W.</u>	K3
2. PROPERTY CONTROLLING IN SECTION <u>24</u>	T. <u>51</u> N. <u>8</u> , R. <u>40</u> E. <u>W.</u>	3
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____, R. _____ E. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Keith L. Sackett do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on January 19 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner K-8: Original monument and accessories not found. Found old north-south blazed line.
- Corner 3: Not set on original survey nor subsequently apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner K-8: Re-established on line between section corners.
- Corner 3: Established on line between section corner north and $\frac{1}{4}$ corner south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Corner K-8: Set 1" I.D. by 5 foot long iron pipe.
 6" Maple N88°W 17.8 ft. $\frac{1}{4}$ S, MBT
 5" Maple S79°E 27.1 ft. $\frac{1}{4}$ S, NBT
 6" Maple N53°W 1.9 ft. Squared and marked $\frac{1}{4}$, 23, 24
- Corner 3: Set 1" I.D. by 5 foot long iron pipe.
 4" Maple N05°E 16.4 ft. 1/16 S, BT
 5" Maple S60°W 24.7 ft. 1/16 S, BT
 7" Aspen S26°E 12.2 ft. 1/16 S, BT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR DATE _____

Keith L. Sackett

SURVEYOR'S MICHIGAN REGISTRATION NO. 10000

