

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>51</u> N. <u>8</u> , R. <u>40</u> E. <u>W.</u>	<u>K-10, K-11, K-12</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner K-10: Original monument and accessories not found.
- Corner K-11: Original monument and accessories not found. Found old down fence in area.
- Corner K-12: Original monument and accessories not found.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner K-10: Re-established 11-10-76 on line between section corners north and south.
- Corner K-11: Re-established 11-4-76 near old fence corner. Fits good with other corners in area and land calls.
- Corner K-12: Re-established 11-4-76 on line between section corners north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|--|
| <p><u>Corner K-10</u>: Set 1" I.D. x 36" I.P. with 4" aluminum cap.</p> <ul style="list-style-type: none"> 3" Maple N59°W 24.3 ft. 1/2S, NBT 3" Maple S28°E 38.1 ft. 1/2S, NBT 8" Aspen N67°E 11.6 ft. 1/2S, NBT 4" Aspen N31°W 6.9 ft. Squared | <p><u>Corner K-11</u>: Set 1" I.D. x 36" I.P. with 4" aluminum cap.</p> <ul style="list-style-type: none"> 7" Aspen S50°W 13.5 ft. S35, NBT 6" Aspen N65°E 15.8 ft. S25, NBT 5" Elm N41°W 45.4 ft. S26, NBT <p><u>Corner K-12</u>: Set 1" I.D. x 36" I.P. with 4" aluminum cap.</p> <ul style="list-style-type: none"> 9" Sugar S47°E 21.1 ft. 1/2S, NBT 5" Sugar N37°E 20.2 ft. 1/2S, NBT 5" Sugar N21°W 13.2 ft. 1/2S, NBT |
|---|--|

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY Michael W. Roose Michael W. Roose DATE 12/28/76

APPROVED AND SIGNED BY Keith L. Sackett DATE December 28, 1976
MICHIGAN REGISTERED LAND SURVEYOR
 Keith L. Sackett

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

