

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>51</u> N. S. R. <u>40</u> W. ^X	<u>I-7, K-7</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 15, 19 76, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner I-7: Original monument and accessories not found.

Corner K-7: Original monument and accessories not found. Found 36" long re-bar set by Billy Buckler, R. L. S.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner I-7: Re-established at location pointed out by local residents. Corner falls in center of gravel road in line with fence south and old road north. Corner fits good with other corners in the area.

Corner K-7: Re-established corner at re-bar. Corner fits good with other corners in the area.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner I-7: Set 1" I.D. x 24" iron pipe with 4" aluminum cap.
Fence corner post S20°W 30.4'
Power pole N78°E 134.1'

Corner K-7: Set 1" I.D. x 24" iron pipe with 4" aluminum cap.
10" Ash S58°W 30.8' S23, NBT
7" Ash N82°W 46.9' S14, NBT
Fence corner North 22'

SIGNED BY _____ DATE _____


SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
DATE 8/11/76
Keith L. Sackett



SURVEYOR'S MICHIGAN REGISTRATION NO. 19006