

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>51</u> ^{N.} / _{W.} , R. <u>40</u> ^{N.} / _{W.}	<u>K-13, L-13</u>
2. PROPERTY CONTROLLING IN SECTION <u>35</u>	T. <u>51</u> ^{N.} / _{W.} , R. <u>40</u> ^{N.} / _{W.}	<u>16</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____, R. _____, S. _____, E. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner K-13: Original monument and accessories not found.
- Corner L-13: Original monument and accessories not found.
- Corner 16: Not set on original survey nor subsequently apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner K-13: Reestablished 8/25/76 between corners east and west.
- Corner L-13: Reestablished 8/25/76 on line between corners east and west.
- Corner 16: Established 8/25/76 on line between corners east and west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|--|
| <p><u>Corner K-13:</u> Set 1" I.D. x 36" iron pipe with 4" aluminum cap.</p> <ul style="list-style-type: none"> 4" Sugar N40°E 9.4' S36, NBT 6" Maple N71°W 31.4' S35, NBT 4" Sugar S40°E 16.9' S05, NBT 7" Square Aspen S69°E 5" <p><u>Corner L-13:</u> Set 1" I.D. x 36" iron pipe with 4" aluminum cap.</p> <ul style="list-style-type: none"> 6" Maple S08°E 10.8' ½S, NBT 3" Sugar N42°E 23.3' ½S, NBT 5" Ash N38°W 31.7' | <p><u>Corner 16:</u> Set 1" I.D. x 36" iron pipe with 4" aluminum cap.</p> <ul style="list-style-type: none"> 7" Sugar N33°W 15.7' 1/16S, BT 4" Ash S01°W 11.9' 1/16S, BT 6" Ash N69°E 4.7' 1/16S, BT Square Aspen 7" N37°E 2.1' |
|---|--|

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 8/30/76
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

