

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 51 <sup>N.</sup> / <sub>S.</sub> , R. 40 <sup>E.</sup> / <sub>W.</sub>	K-13, L-13
2. PROPERTY CONTROLLING IN SECTION	35, T. 51 <sup>N.</sup> / <sub>S.</sub> , R. 40 <sup>E.</sup> / <sub>W.</sub>	16
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____, R. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- Corner K-13: Original monument and accessories not found.
- Corner L-13: Original monument and accessories not found.
- Corner 16: Not set on original survey nor subsequently apparently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- Corner K-13: Reestablished 8/25/76 between corners east and west.
- Corner L-13: Reestablished 8/25/76 on line between corners east and west.
- Corner 16: Established 8/25/76 on line between corners east and west.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- |   |  |
|---|--|
| <p><u>Corner K-13</u>: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.</p> <ul style="list-style-type: none"> <li>4" Red Maple N10°W 10.6' S35, NBT</li> <li>4" Red Maple N78°E 35.4' S36, NBT</li> <li>5" H. Maple S72°E 40.9' S5, NBT</li> <li>3" Ironwood squared S07°E 3.4'</li> </ul> <p><u>Corner L-13</u>: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.</p> <ul style="list-style-type: none"> <li>3" Sugar N39°W 21.6' 1/4S, NBT</li> <li>5" Sugar S65°W 28.9' 1/4S, NBT</li> <li>3" Maple N80°E 9.5' 1/4S, NBT</li> </ul> | <p><u>Corner 16</u>: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.</p> <ul style="list-style-type: none"> <li>5" Ash N84°E 28.0' 1/16S, BT</li> <li>6" Ash S01°E 10.8' 1/16S, BT</li> <li>5" Basswood N82°W 14.9' 1/16S, BT</li> </ul> |
|---|--|


SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET