

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>51</u> ^{N.} X. , R. <u>40</u> ^{X.} W.	<u>I-8, I-9, I-11</u>
2. PROPERTY CONTROLLING IN SECTION <u>23</u>	, T. <u>51</u> ^{N.} X. , R. <u>40</u> ^{X.} W.	<u>3</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ ^{N.} X. , R. _____ ^{E.} W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on See below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner I-8: Original monument and accessories not found. Found old fences north, south and west.
Corner I-9: Original monument and accessories not found. Found old fence to the north.
Corner I-11: Original monument and accessories not found. Found old blazed line going north and south.
Corner 3: Not set on original survey nor subsequently apparently. We found old fence line north and south.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner I-8: Reestablished 8/24/76 at fence corner. Corner fits good with section corners north and south.
Corner I-9: Reestablished 8/18/76 in center of county road east and west in line with fence north. Corner fits good with other corners in the area.
Corner I-11: Reestablished 8/18/76 by double proportion measurement.
Corner 3: Established 8/26/76 on line between section corner north and quarter corner south. Corner falls in old north-south fence line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|--|
| <p><u>Corner I-8:</u> Set 1" I.D. x 36" iron pipe with 4" aluminum cap.
 16" Elm S04°E 23.9' ¼S, NBT
 8" Ash N56°W 20.9' ¼S, NBT
 6" Y. Birch N32°E 21.5' ¼S, NBT
 Square Ash N30°E 4.2'</p> | <p><u>Corner I-11:</u> Set 1" I.D. x 24" iron pipe with 4" aluminum cap in center of old logging road.
 7" Elm N42°E 19.7' S26, NBT
 8" Ash S74°E 26.5' S35, NBT
 8" Elm S57°W 41.2 S34, NBT</p> |
| <p><u>Corner I-9:</u> Set 1" I.D. x 24" iron pipe with 4" aluminum cap in center of county road.
 14" Elm S16°W 48.4' S27, NBT
 5" Aspen S35°E 43.2' S26, NBT
 Fence corner post north 35.1'</p> | <p><u>Corner 3:</u> Set 1" I.D. x 36" iron pipe with 4" aluminum cap.
 10" Elm S53°W 3.1' 1/16S, BT
 5" Maple S12°E 57.2' 1/16S, BT
 5" Maple N43°E 60.8' 1/16S, BT</p> |
- SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 8/30/76
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

