

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Ontonagon Located In: _____ Corner Code # _____
 (County)

- | | | | | | | |
|--------------------------------------|---|------------|---|------------|--------------|-------|
| 1. Public Land Survey | T | <u>51N</u> | R | <u>40W</u> | <u>A-3</u> ✓ | |
| | T | <u>51N</u> | R | <u>41W</u> | <u>M-3</u> | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| 2. Property Controlling in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |
| 3. Miscellaneous Property in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |
4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

SURVEY & REMONUMENTATION

MAY 22 1997

COMMISSION

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Joseph C. Domitrovich, in a field survey on September 26, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A-3) Corner Common to Sections 6 & 7, T51N, R40W, and Sections 1 & 12, T51N, R41W

1845 - William A. Burt set post

16" Hemlock S 53° W 16 links

10" Cedar N 45° W 19 links

1940 - T.H. Wilcox, in Supervisor's Plat of Government Lots 3 & 4, Section 6, T51N, R40W, shows the corner as a concrete monument and also shows concrete monument 33' to the East.

1969 - M.S.H.D., in M-64 Highway Plans, show corner as a 1 1/2" iron shaft and give angle and distance off centerline and two witnesses.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original corner and accessories have been obliterated by road construction. I found a bent iron bar under pavement, which matched the angle and distance off centerline. I also found a square concrete monument 33.06' to the East as called for in plat.

I accepted the iron bar as the corner and placed a 5/8" x 24" rebar over it.

Research on file with County Remonumentation Representative.

PEER GROUP APPROVED
Earl W. Applekamp
 COUNTY REPRESENTATIVE 10-16-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 5/8" x 24" rebar with a 3" diameter aluminum cap stamped to read: S.1, S. 6, S. 12, S. 7; T.51N, R.40W;R.41W;1996; P.S. 37273; COUNTY REMONUMENTATION. Corner falls 5' East of centerline Townline Rd. I established a Reference Monument (R.M.) to the West, a 2" x 30" aluminum pipe with 3" diameter aluminum cap stamped to indicate the corner is 34.30' to the East.

Witnesses:

Aluminum NGS Monument	N 76° 05' 50" E	25.90'
NE Corner Church Steps	S 39° W	76.65'
R.M.	N 89° 54' 06" W	34.30'
Power Pole	N 85° W	33.92'
Aluminum NGS Monument	N 50° 03' 10"W	46.52'
Power Pole	N 72° E	26.45'

NOTE: Bearings are magnetic. Distances are to nail in side of witness objects unless noted.

Signed by J. C. Domitrovich

Date 10/15/96

Surveyor's Michigan License No. 37273

