

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in Ontonagon Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey T 51N R 41W M-7  
 T 51N R 40W (A-7)✓  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

**SURVEY & REMONUMENTATION**  
 MAY 22 1997  
**COMMISSION**  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2						
3											
4	7	6	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

~~One-quarter~~ section corner common to Sections 13, 18, 24, 19, T51N, R41W.

I, John R. Garske, in a field survey on July 17, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

In 1845 Austin Burt, U.S. Deputy Surveyor, set a wooden post from which an 8" maple bears S25°W - 25 links (16.50') and a 12" Lynn - N20°W - 29 links (19.14').

1994± - Survey by Earl Applekamp, RLS, indicates he set a R.R. spike at the corner location.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

I found the spike set by Earl Applekamp in a survey of Section 19, T51N, 40W. The corner falls at the centerline intersection of Townline Road with fence lines running east and west. Distances to other corners used north and west along with discussing the corner position with Mr. Applekamp were used to verify the R.R. spike. This location has been used and accepted and fits local occupation lines very well.

Record research on file.

PEER GROUP APPROVED  
Earl W. Applekamp 8-14-96  
 COUNTY REGISTER

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I established the following reference objects:

- P. pole - S07°E - 124.50 feet
- 8" Aspen - N58°W - 63.23 feet

Set a reference monument consisting of a 2 1/2" aluminum pipe with 3 1/4" aluminum cap stamped: County remonumentation, T51N, R41W-R40W, R.M., S-13, S-18, S-24, S-19, 1996, R.L.S. 28410, east, 30.15 feet, S66°W, 32.75 feet with steel sign rail 0.84 feet away.

Another stamped the same as above except S66°W, 32.75 feet with steel sign rail 0.84 feet away.

SEE SKETCH ON BACK

Signed by John R. Garske  
 Surveyor's Michigan License No. 28410

Date \_\_\_\_\_

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983